

Textile coverings

Final cleaning after construction has been completed, initial cleaning

Clean using high-performance brush vacuum for normal levels of soiling. Dry clean additionally if there are stubborn stains.

On-going cleaning

Clean regularly with high-performance brush vacuum cleaner.

Intermediate cleaning

Clean with high-performance brush vacuum cleaner or dry clean.

Basic cleaning

Clean with high-performance brush vacuum cleaner or dry clean.

Spray extract if necessary if there is very heavy soiling. A test should in any case be carried out on a small area before spray extraction to prevent any damage to the covering or damage caused by excessive use of water.

Parquet, sealed at the factory

Final cleaning after construction has been completed, initial cleaning

Remove coarse and fine dust with vacuum cleaner or wipe with damp cloth. Do not wipe dry in order to avoid damage to the seal (scratches). Remove the panel for re-sealing if there is serious damage to the seal.

Basic treatment

Hot wax: Hot wax once or twice and polish with polishing brush.

On-going cleaning

Wipe with damp disposable cloth or gauze.

Intermediate cleaning, basic cleaning

Wipe with damp disposable cloth or gauze.

Spray clean with liquid hard wax or cold wax.

Important information

The seal protects the wooden floor against penetration by dirt or liquids. Do not use any gloss dispersions.

Natural and synthetic stone

Cleaning at the end of construction, initial cleaning

Remove coarse and fine dirt with vacuum cleaner. Wipe with gauze, damp cloth or with well-wrung mop.

The panels must be removed and cleaned again individually if this cleaning is insufficient on the installed panels. Removal enables to wet, clean and care for the floor panels more easily.

Basic treatment

Let a specialised company impregnate or seal the floor panels if necessary.

On-going cleaning

Vacuum clean or wipe with damp gauze or cloth.

Intermediate cleaning, basic cleaning

Vacuum clean or wipe with damp gauze or cloth. Spray clean with machine if necessary.